## **UNITED KINGDOM**

## SIDEWAY-FORCE SKID RESISTANCE SURVEY DEVICES ACCREDITATION TRIAL SUMMARY TEST CERTIFICATE

Report No: 0127SKID/W965 SVG Issue 6

REGISTRATION NUMBER: W965 SVG TRIAL Reference No: 1

Operated by PTS

Of Britannia House, 1 Rough Hey Road, Grimsargh, Preston

has participated in a United Kingdom Sideway-Force Coefficient Routine Investigation Machine Accreditation check on **28 April 2020** on the Network Route north of Nuneaton assessed by TRL.

Due to the current public health situation regarding COVID-19 it has been deemed unsuitable for a full Accreditation trial to be held at this time. As such a temporary amended approach has been implemented to check the continued consistency of these devices. The above machine has therefore only been tested against the wheel weight and live traffic route criteria specified in Accreditation and Quality Assurance of Sideways Force Skid Resistance Survey Devices document<sup>1</sup> (dated June 2020). Therefore, this certificate should be considered in conjunction with the previous accreditation certificate for this device located at:

http://www.ukroadsliaisongroup.org/en/asset-condition/road-condition-information/data-collection/skid-resistance/Sideway force skid resistance survey devices/index.cfm

This machine has sucessfully met the mandatory criteria of this Accreditation check. Some Network Authorities may also require specific level of performance in some or all of the additional tests. The performance of this machine in each test is summarised in the Annex to this test certificate.

This certificate supersedes any previous certificates issued by TRL.

Signed on behalf of TRL Limited

Patrick Werro

Valid From: 30 April 2020 Date of expiry: 8 August 2020

<sup>1</sup> This document is available from TRL or from the following website http://www.ukroadsliaisongroup.org/en/asset-condition/road-condition-information/data-collection/skid-resistance/Sideway force skid resistance survey devices/index.cfm



## **Test Certificate Annex**

The following parameters must be passed to successfully meet the requirements of the accreditation trial.

| Tested Parameter                       | Left wheel   | Right wheel  |
|--|--------------|--------------|
| Skid Resistance                        |              |              |
| Between run standard deviation         | Pass         | Not Assessed |
| Between equipment standard deviation   | Pass         | Not Assessed |
| Distance measurement and Vehicle Speed |              |              |
| Distance measured                      | Not Assessed |              |
| Vehicle Speed                          | Not Assessed |              |
| Test wheel weight and water flow       |              |              |
| Test wheel weight                      | 203.1        | Not Assessed |
| Wa <mark>ter flow r</mark> ate         | Not Assessed | Not Assessed |
| Water flow direction                   | Not Assessed | Not Assessed |
| * Comments:                            |              |              |

The following parameters were also tested/reviewed. They are not currently mandatory requirements, however some Network Authorities may also require specific level of performance in some or all of these additional tests.

| Not Assessed |  |
|--------------|--|
| Not Assessed |  |
| Satisfactory |  |
|              |  |
|              |  |

